

Remediation of Drainage Issues First United Methodist Church Mt. Vernon, Texas



Flooding was occurring along both the east and west entrances to the church. Hayter Engineering assisted the church to correct this problem.

Improvements started with the existing concrete being removed and disposed of. Installed were: new 4 inch thick concrete paving and retaining wall; 10" HDPE pipe; new curb & gutter; two catch basins; and two light poles were removed and replaced.

The surrounding landscaping and flower bed grading were also performed.

Services provided by Hayter Engineering are listed at right.

The project was completed in 2016.

CLIENT

First United Methodist Church
Mt. Vernon, Texas

CONTACT

Randall Byrd, Chair of Trustees,
FUMCMV
Telephone: 817-245-3736
Email: rbyrd@avantdg.com

CONSTRUCTION COST

\$39,705.00

SERVICES PROVIDED

Design Surveys
Design Plans & Specifications
Construction Review