

## Lamar County Water Supply District Tigertown Booster Pump Station Ground Storage Tank & Water Transmission Main



The Lamar County WSD Water System Master Plan Update identified the Tigertown area in System 1 & 2 as a high priority project due to the low water pressures in the area. Recommended improvements include re-activation of the Tigertown booster pump station, with new storage and approximately 20,000 linear feet of supply pipeline from the Maxey standpipe.

Improvements included:

- 6" Water Transmission Main: 19,651 linear feet of 6" water line.
- Pump Station: Two 25 HP, 3 PH, 460V, 3600 RPM, ODP motor; interior and yard piping and appurtenances.
- 50,000 Gallon Ground Storage Tank.

Services provided by Hayter Engineering are listed at right.

This project was completed in 2016.

### CLIENT

Lamar County Water Supply District  
(LCWSD)

### CONTACT

David Pitcock, Manager  
Telephone: (903) 785-5586  
E-mail: [dwpitcock@yahoo.com](mailto:dwpitcock@yahoo.com)

### CONSTRUCTION COST:

Water Transmission Main: \$281,121  
Ground Storage Tank: \$119,244  
Pump Station: \$104,991

### SERVICES PROVIDED:

Civil Design  
Cost Estimating  
Design Surveying  
Topographic Surveying  
Construction Bid & Award  
Construction Review  
Record Drawings  
One-Year Warranty Review